


Always check the website for the most updated specifications: [www.americh.com](http://www.americh.com)



Tub pictured with optional grab bars and waste & overflow.



All bathtub dimensions are ± 1/2".

**CODES AND COMPLIANCE**

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories - Canada (cUL)
- Canadian Standards Association - (CSA)
- ANSI Z124.1 • ANSI A112-19.7
- ANSI A112.19.8 • ASTM F462-79

Contact Americh for additional approvals.

**MATERIAL**

Acrylic

**DIMENSIONS**

66" x 34" x 20" (1676 x 864 x 508 mm)


Whirlpool Operating Gallons = 50 (Liters = 189)

Gallon to Overflow = 70 (Liters = 265)


**ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.


**Builder Series**



**Luxury Series**




**Platinum Series**




**Combination**


(pump and blower location only)



**Airbath System II**



**Airbath System III**



**LEGEND:**

- P PUMP
- B BLOWER
- JET
- ROTARY JET
- DUAL SUCTION
- LIGHT
- ON/OFF CONTROL
- GRAB BAR
- ACCESS PANEL (MINIMUM 16" X 20")

**ACCESSORIES**

| Apron | Grab Bars |     |     |         |      | Pillow |     |       |                     | Tile Flange | Installation |            |
|-------|-----------|-----|-----|---------|------|--------|-----|-------|---------------------|-------------|--------------|------------|
|       | 9"        | 14" | 16" | Madison | Rail | 13"    | 17" | Angle | Head Support System |             | Deckmount    | Undermount |
| •     | •         | •   | •   |         |      | •      |     | •     | •                   | •           | Yes          | Yes        |

• = option is available    = standard on Platinum Series    = option is not available

**INSTALLATION TIPS**

- Install product according to Owners Manual and local codes.
- All units with an Airbath III may be 1 1/2 - 2 1/2" higher than stated.
- Any whirlpool or Airbath® unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater. Always consult your local plumber for recommendations as installations will vary.
- When ordering for undermount installation, always advise Americh to assure there are no issues with deck mounted controls.
- Dimensions for undermount installation should be taken directly from the bathtub.
- Cut-out dimension: 64" x 32"